

15-159-60001-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
No. Broadway  
Topeka, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 9 Twp. 18S Rge. (E) 10 (W)

Location as "NE/CNW/SW" or footage from lines NE SW SW

Lease Owner Chief Drilling Co., Inc.

Lease Name Habiger Well No. 1

Office Address Box 797 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9/5 19 62

Application for plugging filed 9/5 19 62

Application for plugging approved 9/5 19 62

Plugging commenced 9/5 19 62

Plugging completed 9/5 19 62

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Loman - Holyrood, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3280 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Gravel		0	193		193	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set wooden plug at 185' with 20 sacks cement through drill pipe; 1/3 sacks hulls, set wooden plug at 35' with 8 sacks cement.

Stamp: 1052  
9-7-62  
CONSERVATION DIVISION  
TOPEKA, KANSAS

Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Box 797 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
V. Richard Hoover, Pres. Chief Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard Hoover  
Box 797 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September 19 62

My commission expires Jan. 26, 1963.  
Carmen Reinhardt Leiker, Notary Public.

WELL LOG

Chief Drilling Co., Inc.  
Box 797  
Great Bend, Kansas

HABIGER #1  
NE SW SW Sec. 9-18S-10W  
Rice County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 8-29-62  
Completed: 9-5-62

RECEIVED  
STATE CORPORATION COMMISSION

Casing Record: 8-5/8" @ 193' w/170 sacks Sunset Cement.

SEP 7 1962

CONSERVATION DIVISION  
Wichita, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale	0	193	1759 Gr.
Red Bed & Shale	193	483	1761 D.F.
Anhydrite	483	502	1764 K.B.
Shale & Shells	502	1350	
Shale & Lime Streaks	1350	2750	
Lime	2750	2810	
Lime & Shale	2810	2930	
Lime	2930	3247	
Dolomite	3247	3280	
Total Depth	3280		

FORMATION TOPS

Anhydrite	483	+1281
Topeka	2532	- 768
Heebner	2793	-1029
Toronto	2812	-1048
Douglas	2822	-1058
Brown Lime	2912	-1148
Lansing	2928	-1164
Base Kansas City	3199	-1435
Conglomerate	3233	-1469
Arbuckle	3247	-1483
Total Depth	3280	-1516

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE SW SW Sec. 9-18S-10W, Rice County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 5th day of September, 1962.

*Carmen Reinhardt Leiker*  
Carmen Reinhardt Leiker, Notary Public

My commission expires: Jan. 26, 1963.