

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Building
Wichita, Kansas 67202
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-159-60001-00-01
API NUMBER _____

LEASE NAME Cody-Habiger

WELL NUMBER #1 (OWWO)

990 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 9 TWP. 18 RGE. 10 (E) or (W)

COUNTY Rice

Date Well Completed 9-13-62

Plugging Commenced 6-29-88

Plugging Completed 10-7-88

OCT 20 1988
10-20-88
CONSERVATION DIVISION
Wichita, Kansas

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John J. Darrah, Jr.

ADDRESS 412 E. Douglas, Suite #1, Wichita, Ks 67202

PHONE# (316-263-2243) OPERATORS LICENSE NO. 5088

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 8, 1988 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 3311'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	193'	None
				5-1/2"	3266'	2,163.22'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 2940' and 5 sacks cement. Shot casing at 2500' and 2150'. Pulled 68 joints of 5-1/2" casing. Howco plugged well with 400# hulls, 25 sacks gel, 100# hulls and 125 sacks 60/40 pozmix cement with 2% gel. Maximum pressure was 700 psi and shutin 600 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. "Bo" Darrah, Jr.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1988

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 4-26-91

Iona M. Leatherman
Notary Public

My Commission Expires _____