

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-30122-0000

LEASE NAME Kane

WELL NUMBER "C" #1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 18 TWP. 30 RGE. 17 (E) or (W)

COUNTY Kiowa

Date Well Completed 4-27-66

Plugging Commenced 5-23-91

Plugging Completed 6-5-91

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Rockhold Engineering, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# (316-792-2506) OPERATORS LICENSE NO. 5111

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 23, 1991 (date)

by Casey Morris (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5113'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	533'	None
				4-1/2"	5110'	2,766.85'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 4950', and 1/4 sacks cement. Shot casing at 4227', 3736', 3219' & 2748'. Pulled 84 joints of 4-1/2" casing. Allied plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, 8-5/8" plug and 150 sacks 60/40 poxmix with 6% gel, Maximum pressure was 600 psi and 200 psi shutin.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) Box 698, Gt. Bend, Ks. 67530

RECEIVED  
STATE CORPORATION COMMISSION

JUN 07 1991

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1991

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires \_\_\_\_\_

STATE NOTARY PUBLIC  
KANSAS  
IGNA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-91

Iona M. Leatherman  
Notary Public