


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 32 Twp. 24S Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines NW-NW-NE
Lease Owner Sunray Mid-Continent Oil Company
Lease Name McConnaughey Well No. 1
Office Address Box # 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Nov. 9, 1958
Application for plugging filed Nov. 10, 1958
Application for plugging approved Nov. 12, 1958
Plugging commenced Nov. 9, 1958
Plugging completed Nov. 9, 1958
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud to 240', 1/4 sack hulls, wood plug & 30 sacks cement. Filled hole w/mud to 40', 1/2 sack hulls, wood plug & 15 sacks cement. Cement to surface, plugging completed.

Log attached.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Co.
Address _____

STATE OF KANSAS, COUNTY OF BARTON, ss.
N. E. Montgomery (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery
Box # 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of November, 1958

My commission expires Dec. 24, 1960 Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
PLUGGING
FILE SEC 32 T. 24 R. 12W
BOOK PAGE 144 LINE 33 CONSERVATION DIVISION
Wichita, Kansas
NOV 15 1958

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
November 12, 1958

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: October 27, 1958
Drilling Completed: November 9, 1958

McConnaughey #1 NE/4 Section
32-24S-12W, Stafford County,
Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation:

Surface	0
Sand	150
Shale & Shells	300
Red Bed & Shale	715
Anhydrite	740
Shale & Shells	1680
Shale & Lime	1800
Lime & Broken Shale	1975
Lime & Shale	2265
Shale & Lime	3035
Lime & Shale	3140
Lime	3205
Lime & Shale	3615
Lime	3890
Conglomerate	3974
Viola	4050
Viola Chert & Shale	4067
Cherty Lime	4100
Sand	4106
Cherty Lime & Shale	4140
Sandy Shale	4163
Arbuckle	4200 TD

I, Fred E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's McConnaughey #1 NE/4 Section 32-24S-12W, Stafford County, Kansas.

Fred E. Stickle
Fred E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

PLUGGING	
FILE	SEC 32 T 24 R 12W
BOOK	PAGE 144 LINE 33