

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

9-22-82

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. George Nicholas of Nicholas Casmy Plugging has this date requested permission to plug the following described well:

Operator's Full Name: Africo Explorations Inc., Ltd.

Complete Address: 122 North Greenwood, Tulsa, Oklahoma 74120

Lease Name: Johnson "B" Well No. 4

Location: SW SE NE Sec. 5 Twp. 24 Rge. 4 (E) (W)

County: Renov Total Depth: 480'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: Lost Hole (Lost Circulation) (7-81)

Mr. Nicholas was instructed to plug the well as follows:

Pull 12.5 drill collars - sub and 13 3/8" bit. Run tubing to 372'
Pump 100 sacks common cement through tubing at 372'. Pull
2" tubing to 252'. Pump 100 sacks common cement through tubing
at 252'. Pull tubing. Run 2 Joints 4 1/2" casing circulate
casing with cement inside and out. Cut off 3' below
ground level.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

OCT 05 1982

CONSERVATION DIVISION
WICHITA, KANSAS

Conservation Division Agent