

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

11-1-1966

NOV 1 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ray Rice of Sterling Drilling Co. has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name: Johnson "I" Well No. 1

150' Southwest of

Location: C SW NE Sec. 5 Twp. 24 Rge. 4 (E)(W)X

County Reno Total Depth 3405' Oil Well

Gas Well    Input Well    SWD Well    D & A X    Lost Hole   

Mr. Rice was instructed to plug the well as follows:

(Plugging in 7" Surface Pipe) Fill hole with mud to 560'. Push plug and 1/4 sack hulls to 560' and cement hole with 10 sacks through drill pipe. Fill hole with mud to 300'. Push plug and 1/4 sack hulls to 300' and cement hole with 10 sacks through drill pipe. Fill hole with mud to 35'. Push plug and 1/4 sack hulls to 35' and cap hole with 5 sacks

cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,  
[Signature]  
Conservation Division Agent