

15095001100000

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1963
8-8-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Don F. Moore

Complete Address: 918 Central Bldg., Wichita, Kansas

Lease Name: Fay Well No. # 1

Location: SW NE Sec. 15 Twp. 28 Rge. 6 (E) (W) W

County Kingman Total Depth 4260 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Watson was instructed to plug the well as follows:

211' of 8 5/8" surface pipe, cemented with 175 sacks.

4018' of 5 1/2" long string, cemented with 100 sacks. Plugged

back to 3885'. Top perforation 3881'. Sand to 3870', cement

with 5 sacks. Fill hole with mud to 250', 10' rock bridge,

cement with 20 sacks. Fill hole with mud to 40', 10' rock

bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent