



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 18 1962
 7-18-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 7-14-1962, 1961, authorized the following plugging operation:

Operator's full Name: Beardmore Drilling Co.

Complete Address: 827 Beacon Building, Wichita, Kan,

Lease Name: Brown "A" Well No. 1

Location: C NW SE Sec. 15 Twp. 28 S Rge. 6 (E)(W)XX

County: Kingman Total Depth: 3927'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated:

Operator was instructed to plug well as follows:

202' of 8 5/8" surface pipe circulated with 175 sacks cement.

Hole filled with heavy drilling mud to 175'. 1/2 sack hulls, 1st

cementing plug and 20 sacks cement through drill pipe. Hole

filled to 40' with heavy drilling mud. 1/2 sack hulls and 2nd

cementing plug and 10 sacks cement to bottom of cellar.

Rathole bridged and 2 sacks Very truly yours,
 cement.

Herman Justus

