



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP-10 1962
 9-10-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date September 4, 1962, authorized
 the following plugging operation:

Operator's full Name: Chief Drilling Co., Inc.

Complete Address: Box 787, Great Bend, Kansas

Lease Name: Habiger Well No. 1

Location: NE SW SW Sec. 9 Twp. 18 Rge. 10 (E) (W)

County Rice Total Depth 3280'

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Circulate Heavy mud. Fill hole with mud to 185'. Push
plug and 1/4 sack hulls to 185' and cement with 20 sacks
thru drill pipe. Fill hole with mud to 25'. Push plug
and 1/4 sack hulls to 25' and cap hole with 8 sacks.

Bridge, and cement rathole with 2 sacks.

Very truly yours,

Arthur J. Tomer
 Conservation Division Agent