

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 095-20798-0000 (of this well)

Operator's Full Name Patton Oil Co.

Complete Address 5660 S. Syracuse Circle, Suite 200, Englewood, Co. 80110

Lease Name Sale Well No. 1

Location C SE SE Sec. 11 Twp 27S Rge. 10 (E) (W) X

County Kingman Total Depth 2435

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 3 Pm. Day 22 Month 5 Year 1980

The above well was plugged as follows:

263' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 2434' w/225  
sax cement. Plug back to 1640'-Preforated at 1594' to 1604'-Sand  
back to 1575'-Top sand w/ 4 sax mixed cement w/ dump bailer. Pull  
1305' casing-Allied mixed & pumped in 8 5/8" casing 8 sax hulls-  
25 sax gel-100 sax 50/50 posmix cement w/4% gel & 3% cc to top of  
casing. Shut in w/ 100# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED RECEIVED  
STATE CORPORATION COMMISSION

DATE 5-30-80

INV. NO. 2249-w

MAY 27 1980  
CONSERVATION DIVISION  
Wichita, Kansas

05-27-80