

15-095-19122-0000

Form CP-3  
Rev. 6-26-62

KANSAS

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued September 6, 1967.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 29 1967

09-29-67

CONSERVATION DIVISION

Operator's Full Name California-Time Petroleum Company c/o Peter Gates

Complete Address: 1651 South B Street, Blackwell, Oklahoma 74631

Lease Name Bradshaw Well No. # 1

Location C SW SE Sec. 12 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 4366'

Abandoned Oil Well Gas Well  Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Globe Cementing Company

Address: Kiowa, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 3:45 PM Day 26th Month Sept. Year 1967

The Above well was plugged as follows:

330' of 8 5/8" surface pipe, cemented with 175 sacks. 4358' of 5 1/2" long string,  
cemented with 300 sacks. All perforations below had been squeezed. Plug back T.D.  
1655'. Pipe was perforated at 1655' to get cement behind the pipe. 150 sacks of  
cement was pumped at 1655', circulating cement from 1655' to the top of the surface  
pipe. Pipe was reperforated from 1598' to the top perforation at 1589'. 340 sacks  
of cement was pumped into the 5 1/2" long string, through a 5 1/2" swage, to a pressure  
100 lbs., bringing the cement to the base of the cellar.

No recovery of any pipe.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Audie Elving  
Well Plugging Supervisor

DATE 9/29/67

INV. NO. 6405-W