

State of Kansas



15-095-20328-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 P. O. Box 17027 3830 S. Meridian
 WICHITA, KANSAS 67217

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 29 1974
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg Inc has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Hershberger Enterprises

Complete Address: 230 O.W. Garvey Bldg Wichita, KS

Lease Name: Reno Well No. 1

Location: NE/NE/NW Sec. 33 Twp. 27 Rge. 5 (E)(W) W

County: Kingman Total Depth 3785 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

213 ft 8 5/8 surface cemented with 180 sacks. Fill hole
to 200 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to
40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

[Signature]
 Conservation Division Agent