

State of Kansas



15-155-02093-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1967
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

March 27, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Louis Short

Complete Address: Burrton, Kansas

Lease Name: Hensley Well No. 1

Location: SE NW SE Sec. 14 Twp. 23 Rge. 4 (E)(W) X

County Reno Total Depth 3590' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3570' and cement with 5 sacks.

Fill hole with mud to 250'. Set rock bridge from 250' to 240' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge

from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

William J. Thomas
Conservation Division Agent