

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

RENO County. Sec. 14 Twp. 23S Rge. (E) 4 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE SE NE 1/4

Lease Owner. OILSON OIL COMPANY

Lease Name. E. R. Downie Well No. 5

Office Address. Drawer 588, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Oil & Gas

Date, well completed. 3 - 29 - 19 35

Application for plugging filed. 11 - 19 - 19 40

Application for plugging approved. 11 - 20 - 19 40

Plugging Commenced. 11 - 21 - 19 40

Plugging Completed. 11 - 29 - 19 40

Reason for abandonment of well or producing formation. Well went to water

If a producing well is abandoned, date of last production. 1 - 3 - 19 40

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Ruel Durkee

Producing formation. Chat Depth to top. 3265 Bottom. 3372 Total Depth of Well. 3837 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
Chat	Oil & gas	3265	3372	15 1/2	250	None
Burton	Water	3597		7	3591	2233 ft.
Viola	Water	3715				
Simpson - Wilcox	Water	3736				
Silicious Lime	Water	3829	3837			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Dumped 10 sacks of cement at 3837 T.D. Mudded to 3400 ft. Bridged with rock and dumped 8 sacks of cement. Ripped pipe in Chat, made a well.

11 - 21 - 1940

put in rock and dumped 10 sacks of cement at 3315. Mudded hole to 260 ft. Bridged at 260 ft. put in 10 ft. of rock and dumped 15 sacks of cement. Mudded hole and dumped 10 sacks of cement at base of cellar.



DEC 9 1940  
STATE CORP. COM. DIV.  
CONSERV. DIV.

12-9-1940

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. S. A. Keefover

Address. Box R, Burton, Kansas

STATE OF KANSAS, COUNTY OF RENO, ss.

S. A. Keefover (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Keefover

(Address)

SUBSCRIBED AND SWORN to before me this 6 day of December, 1940.

My commission expires 4/27/42

G. J. Bryant Notary Public




OLSON OIL COMPANY  
E. R. DOWNIE # 5  
SE SE NE 14-23S-4W  
RENO COUNTY, KANSAS

COMMENCED 12 - 1 - 34  
COMPLETED 3 - 29 - 35  
ELEVATION 1473'

0		
180	Sand	3060 Broken lime
235	Sand & shale	3110 Shale
255	Shale	3135 Lime
375	Shale	3170 Lime & shale
782	Shale & shells	3265 Shale
880	Lime	3354 Chat
987	Broken lime	87 Lime
1090	" "	3413 Chat & lime
1302	Shale & shells	3435 Chat
83	Lime & shale	3489 Lime
95	Lime	3597 Shale
1411	Shale	3600 Lime, R.U.S.T.
20	Lime	3602 Lime
30	Shale	3604 H.F.W.
1595	Shale & shells	3617 Lime
1780	Shale	3632 "
1896	Shale & shells	3707 Shale
1975	Shale	3736 Lime
2110	Shale & shells	3742 Sand, H.F.W.
2213	Shale	3784 Sand
80	Shale & lime	3785 Shale
92	Shale	3790 Lime
98	Lime	3794 Shale
2318	Shale	3800 Sand
2421	Lime	3805 Shale
2501	Shale & shells	3817 Shale
63	Lime & shale	3822 Shale, green
70	Lime	24 Lime
97	Shale	3837 Lime, T.D.
2636	Lime	
2742	Lime & shale	Plugged back to 3372
2840	Lime	
50	Shale	
2906	Lime	
28	Broken lime	
43	Lime	
73	Broken Lime	
2996	Lime & shale	
3019	Shale	
3030	Lime	
3050	Shale	

CASING RECORD

15 1/2"	70#	250
7"	24#	3591'



14 23 46  
123 8

Subscribed and sworn to before me  
this 19th day of November, 1940

I hereby certify that the above is  
a true and correct copy of the log of  
E. R. Downie # 5, SE SE NE, Sec. 14  
T 23S, R 4W, Reno County, Kansas

*G. J. Bryant*  
Notary Public

*E. R. Downie*