


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County, Sec. 13 Twp. 23S Rge. 4 W (E) (W)



Locate well correctly on above Section Plat

Location as "NE/CNW&SW" or footage from lines _____
Lease Owner S. & S. Supply Co
Lease Name Sabin Well No. 15
Office Address P.O. Box 2513 Tulsa, Okla
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4-10-50 19____
Application for plugging filed Sept. 3, 1954 19____
Application for plugging approved Sept. 3, 1954 19____
Plugging commenced Sept. 11 19 54
Plugging completed Sept. 18 19 54
Reason for abandonment of well or producing formation Non-Economic

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Mississippian Depth to top 3263 Bottom 3541 Total Depth of Well 3641 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi		3263	3541	8 5/8 5 1/2	284 1/2 3635	None 3181'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back to 3615'. Dumped 6 sacks of cement. Shot pipe off at 3181'. Pulled pipe and mudded hole to 280'. Set rock bridge and dumped 15 sacks of cement. Finished mudding hole and dumped 5 sacks of cement at base of cellar.


Name of Plugging Contractor Bert Self (If additional description is necessary, use BACK of this sheet)
Address R.R. #4 Hutchinson

STATE OF Kansas, COUNTY OF Sedwick, ss. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Schusterman
Tulsa Okla Box 2513
R.R. #4 Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1954
My commission expires Jan. 31, 1957
Pewam S. Greaves

My commission expires _____ Notary Public.



STATE OF _____
10-14-54

15-155-02514-0000

COMPANY: . CRA
FARM: Sabin No. 5
TOTAL DEPTH: 3641'
CONTRACTOR: CRA - Rig #3
COMM: 1-12-50 COMP: 4-10-50
CASING RECORD: 8-5/8" @ 284 1/2' w/200 sks.
5 1/2" @ 3635' w/100 sks.

Sec. 13 TWP. 23 S RGE. 4 W
LOCATION: NW SE NE
COUNTY: Reno
STATE: Kansas
ELEVATION: 11469'
PRODUCTION: 13-1/3 BO, 371 BW
in 24 Hrs.

Figures Indicate Bottom of Formations

soil - sand & clay streaks	133
sand	233
shale & shells	283
shale & sand	488
chalky gyp	508
anhydrite	533
shale & shells	873
sand	893
shale & shells	988
lime & shale breaks	1098
shale & lime shells	1163
shale & shells	1838
lime & shale breaks	2058
lime & shale	2653
lime & shale breaks	2718
lime	2973
lime & shale	3278
lime cherty	3323
lime	3358
lime & chert	3378
lime	3407
lime & shale	3634
lime	3641 RTD d.f.

GEOLOGICAL TOPS D.F.

Lansing-KC	2542'
Mississippian Ls.	3263'
Kinderhook Sh.	3541'
Hunton Ls.	3634'

Plugged back w/lead wool within
1' of casing point.

Perforated 3626'-32' w/24 shots

Perforated 3633 1/2'-36 1/2' w/18 shots

Drill stem test 3344'-68' -
open 1 hour, recovered 50'
gassy oil cut mud.

Drill stem test 3635'-41' -
open 45 minutes, recovered
2520' oil & gas, 300' water

All measurements D.F.

PLUGGING
 SEC 13 T 23 R 4 W
 PAGE 41 LINE 15

DIVISION