

RECEIVED

MAY 24 1971

S & K OIL CO.
K & P OIL CO. CP-4
LOUIS KAHAN, ET, AL


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD 15-155-02515-0000

Reno County. Sec. 24 Twp. 23S Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. SE/4 SE/4
Lease Owner S & K Oil Co P O Box 559 Tulsa, Oklahoma 74101
Lease Name M. E. Sabin Well No. B1
Office Address P. O. Box #682, Tulsa, Oklahoma 74101
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 6-16-33
Application for plugging filed Feb. 5
Application for plugging approved Feb. 8
Plugging commenced April
Plugging completed May 17
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3379 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	263	None
				8 5/8"	3265'	2086.80'
				5 1/2"	3008'	2633.90'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back in the 8 5/8" with gravel at 3200'. Dumped 7 sacks of cement. Shot pipe off at 2633.90(5 1/2"). Pulled pipe. Shot 8 5/8" at 2086.80". Pulled pipe and mudded hole to 225'. Set rock bridge from 225' to 200' and filled surface with 6 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.



STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.
(Signature) Bert Self
R. R. #4, Hutchinson, Kans. 67501
(Address)
Subscribed and sworn to before me this 18th day of May, 19 71

My commission expires October 18, 1973 Notary Public.

WELL RECORD — (Continued)

WELL NO. B-1

LEASE K 3-29

(12) ADDITIONAL INFORMATION

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 8 1971
 CONSERVATION DIVISION
 Wichita, Kansas

(13) MATERIAL LOST IN HOLE

(14) WELL LOG

FORMATION	FROM	TO	NO. OF FEET	DRILL. TIME	FORMATION	FROM	TO	NO. OF FEET	DRILL. TIME
Sand	0	15							
Sand and shale	15	185							
Sand	185	195							
Sand and shale	195	259							
Shale	259	269							
Shale and lime shells	269	882							
Lime	882	905							
Shale and lime shells	905	980							
Lime	980	1000							
Shale	1000	1004							
Sand & lime shells	1004	1247							
Shale	1247	1555							
Shale & lime shells	1555	2096							
Lime	2096	2140							
Shale & lime shells	2140	2780							
Lime	2780	2907							
Broken lime	2907	2914							
Lime	2914	2920							
Shale	2920	2967							
Shale and lime	2967	3026							
Shale and lime shells	3026	3180							
Var. shale	3180	3261							
Chat, set 8 1/2" w/ 250 sacks cement	3261	3280							
Chat, T. D.	3280	3283 3/4							
Sho. of gas	3279	3280							
Inc. of gas	3280	3283							
Inc. of gas	3283	3330							
Oil	3330	3331							
H.F.O.	3331	3349							
Flow by heads - 538 bbls. in 10 hrs.	3349	3379							

Pot. - 918 bbls.