

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER Drilled 2-8-41

LEASE NAME 15-155-02523-0000
Sabin

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 13 TWP. 23 RGE. 4W (E) or (W)

COUNTY Reno

LEASE OPERATOR Howell Oil Co., Inc.

ADDRESS Rt 1, Box 22 Burton, KS 67020

PHONE# (316) 463-2609 OPERATORS LICENSE NO. 5091

Character of Well Oil

Date Well Completed

Plugging Commenced 6-3-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-7-97

The plugging proposal was approved on (date)

by (XCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3384'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	250'	none
				5 1/2	3327'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s'.

Checked hole. TD @ 30'. Tried to "run in 2 3/8" tubing, would not go past 30'. Ran in 1" tubing to 300', plus 3 more fts. Tubing went dead. Dug pit & put in liner. Rig up R & L Swivel. Tried to wash tubing down. Pull 1" out. Tied on to 2 3/8 & drilled down to 457'. Swivel broke down. Next day drilled down to 533'. Perf well at 522', spotted 35 sks cem. Pull tubing to 315'. Perf well at 315' & circulated 305 sks cement from 315' to surface. Pulled tubing out of hole. Plugging complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 931529

Address P.O. Box 467 Chase, Kansas 67524 6-16-97

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Howell Oil Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed & the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 97

Irene Herzberg
 Notary Public

My Commission Expires:

