


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

RENO County. Sec. 13 Twp. 23S Rge. 4 (E) (W) West  
Location as "NE/CNW/SW" or footage from lines: SW SW SW  
Lease Owner: 34 K Oil Co.  
Lease Name: STAN B Well No. 6  
Office Address: Box 682, Tulsa, Oklahoma 74101  
Character of Well (completed as Oil, Gas or Dry Hole): Dry  
Date well completed: Nov 16 1967  
Application for plugging filed: 7-31-68 19    
Application for plugging approved: 8-1-68 19    
Plugging commenced: Aug. 7 1968  
Plugging completed: Aug. 12 1968  
Reason for abandonment of well or producing formation: dry

If a producing well is abandoned, date of last production: 19    
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Hugh Scott  
Producing formation: \_\_\_\_\_ Depth to top: \_\_\_\_\_ Bottom: \_\_\_\_\_ Total Depth of Well: 3343 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	255'	none
				5 1/2"	3327'	2409.85'
Cherokee Shale		3139	3142			
Mississippian Ls		3252	3254			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

\_\_\_\_\_ and dumped 5 sacks of cement.  
Sanded back to 3325'. Shot pipe off at 2409.85'. Pulled pipe and mudded hole to 170', and set 10' rock bridge. Dumped 35 sacks of cement. Mudded to 40' and set 10' rock bridge. Finished mudding and dumped 15 sacks of cement at base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor: Bert Self  
Address: Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans.  
(Address)

Sworn to before me this 29th day of August, 1968  
Dorothy Self  
Notary Public.



DRILLERS LOG  
SABIN "B" NO. 6

15-155-20014-6000

CASING RECORD:	COMPANY:	S & K Oil Co.	DESCRIPTION:
10-3/4" @ 254' w/300 sax cement	CONTRACTOR:	Sage Drilling Co.	SW SW SW Sec. 13-23S-4W Reno County, Kansas
TOTAL DEPTH: 3340'	COMMENCED:	August 14, 1967	
	COMPLETED:	August 20, 1967	

---

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	255	
Shale & Shells	255	485	
Lime & Shale	485	1035	
Shale & Shells	1035	1540	
Shale & Lime	1540	2115	
Lime & Shale.	2115	2880	
Lime	2880	3085	
Lime & Shale	3085	3233	
Shale, Lime & Chert	3233	3340	5½" @ 3327 w/100 sax

---

**RECEIVED**  
STATE CORPORATION COMMISSION  
**AUG 1 1968**  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer  
Wayne W. Kahmeyer

Subscribed and sworn to before me this 24th day of August, 1967.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.