


15-095-20294-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 34 Twp. 27S Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines NW NE SW
Lease Owner National Oil Co., Inc.
Lease Name Allbritten Well No. 1
Office Address 200 W. Douglas, Suite 550, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 19, 19 72
Application for plugging filed December 19, 19 72
Application for plugging approved December 19, 19 72
Plugging commenced December 19, 19 72
Plugging completed December 19, 19 72
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	333'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 300 feet. Followed by wooden plug and 1/2 sack huls. Placed 35 sacks onto huls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack huls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 72

My commission expires May 9, 1975

Betty Brandt
Notary Public.

15-095-20294-0000

R O T A R Y D R I L L E R S ' L O G

OPERATOR: National Oil Co., Inc. DRILLING COMMENCED: December 7, 1972
200 West Douglas, Suite 550
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: December 19, 1972
505 Union Center
Wichita, Kansas 67042

CASING RECORD: 8 Jts. 333' 8-5/8" LOCATION: Allbritten No. 1
cemented with 275 sacks NW NE SW
Section 34-27S-10W
Kingman County, Kansas

0 - 30	River mud	3445 - 3461	Lime & shale
30 - 55	Sand	3461 - 3832	Lime
55 - 333	Red bed	3832 - 3972	Lime & shale
333 - 1033	Red bed & shale	3972 - 3980	Chert
1033 - 1296	Shale & shells	3980 - 3995	Lime
1296 - 1700	Lime & shale	3995 - 4052	Chert & lime
1700 - 2040	Lime	4052 - 4262	Shale
2040 - 2250	Lime & shale	4262 - 4331	Lime & sand
2250 - 2590	Shale & sandy lime	4331 - 4351	Shale & sand
2590 - 2950	Shale & lime	4351 - 4392	Sand & shale
2950 - 3155	Lime & shale	4392 - 4425	Shale
3155 - 3385	Shale & lime	4425 - 4440	Lime
3385 - 3445	Shale & sand	4440	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1972
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 22nd of December, 1972.

Betty Brandt
Betty Brandt Notary Public

My commission expires: May 9, 1975.