

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kingman

County. Sec. 36 Twp. 27S Rge. (E) 10 (W)

Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Donald T. Ingling, et al
Lease Name Schwartz Well No. 1
Office Address 615 First Nat'l Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 18 1968
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced December 18 1968
Plugging completed December 18 1968
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,485 feet (total rotary depth) to 280 feet. Set bottom plug at 280 feet and cemented with 25 sacks of cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 15 sacks of cement, 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.
Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1968

My commission expires April 21, 1971
Martha Hartpence
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15095-20129000

COMPANY Donald T. Ingling, et al

SEC. 36 T. 27S R. 10W

FARM Schwartz NO. 1

LOC. C NE NW

TOTAL DEPTH 4,485'

COUNTY Kingman

COMM. December 5, 1968


COMP. December 18, 1968

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, INC.

ISSUED



CASING

20	10		
15	8-5/8"	288'	cemented w/225 sx cement ELEVATION 1684 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	308		
Shale & Red Bed	990		
Shale & Shells	1650	Brown Lime	3446 - 1762
Lime & Shale	3525	Lansing, K.C.	3458 - 1774
Lime	4030	Mississippi Lime	4001 - 2317
Lime & Chert	4120	Kinderhook Shale	4095 - 2411
Lime	4200	Viola Lime	4295 - 2611
Shale & Lime	4253	Simpson Shale	4364 - 2680
Lime	4307	Simpson Sand	4380 - 2696
Lime & Shale	4380	Arbuckle Lime	4459 - 2775
Lime	4418	Log T.D.	4481 - 2797
Lime & Shale	4463	Rotary T.D.	4485 - 2801
Lime	4485		
Rotary Total Depth	4485		

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

Arlo B. Romer

STATE OF KANSAS

COUNTY OF SEDGWICK

} SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 23rd day of December, 1968.

Martha Hartpence

Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 24 1968
 CONSERVATION DIVISION
 Wichita, Kansas