

15-095-01714-000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 1 Twp. 28 Rge. 5 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. C E/2 NE NE
Lease Owner. The Shallow Water Refining Company
Lease Name. Tract 17 Bartholomew Unit Well No. 1
Office Address. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-13-65 _____ 19____
Plugging completed 9-17-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well H. Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3768 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	197'	None
				5-1/2"	3768'	2938'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3750', sanded hole to 3730' and dumped 5 sacks of cement @ 3730' with dump bailer. Pulled 5 1/2" casing, checked fluid to 400', mudded hole to 190', set rock bridge to 180' and dumped 20 sacks of cement @ 180'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Fred J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 1965

My commission expires May 20, 1968
Milton J. Volin Notary Public.

15-095-01714-0000

Sheet 17

COPY

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WESTGATE-GREENLAND OIL COMPANY
FARM Harding NO. 1

SEC. 1 28 R. 57
LOC. C E/2 NE NE

TOTAL DEPTH 3775
COMM. 11-1-50 COMP. 11-18-50
SHOT OR TREATED
CONTRACTOR Jackson Drilling Corporation
ISSUED 2-3-51

COUNTY Kingman
KANSAS

CASING

8 5/8" 197' cem. w/135 sx
5 1/2" 3768' cem. w/75 sx

ELEVATION 1422

PRODUCTION Pot. 52 bbls. oil

FIGURES INDICATE BOTTOM OF FORMATIONS

All measurements from top of derrick floor

clay & sand 110
shale & lime shells 200
shale & shells 425
salt & shale 675
lime & shale 2460
lime & broken lime 2580
lime & shale 2917
lime 2944
lime & shale 3009
lime 3293
lime & shale 3337
lime 3388
shale & lime 3612
shale & lime, sand 3692
shale & lime 3749
Mississippi lime 3775
Total depth

Tops:
Brown lime 2864
Lansing 2915
Mississippi 3725

Remarks:
Drill stem test 3767-3775.
Open 45 minutes, rec. 30 feet
free oil and 35 feet of muddy
oil. 1,000 gals. Dowell service
flowing 53 barrels oil in 3 hrs.

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1965
CONSERVATION DIVISION
Wichita, Kansas