


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-095-00090-0000

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County. Sec. 1 Twp. 28 Rge. 5 (E) W(W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Bennett & Roberts Drilling, Inc.
Lease Name Baxter Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/19 19 55
Application for plugging filed 3/19 verbally 19 55
Application for plugging approved 3/19 verbally 19 55
Plugging commenced 3/19 19 55
Plugging completed 3/19 19 55
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 143' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged as ordered: Filled hole to surface pipe,
Plug and rock bridge @ 140', 15 sx cmt through
pipe, fill with mud, plug & 5 sx cmt @ top. Top
plug tied with wire.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 19 55

My commission expires 6/17/58 Wara Hummel Notary Public.



03-28-55

15-095-000900000

Bennett & Roberts Drilling, Inc.
Baxter #1

SE NW SE Sec. 1-28-5
Kingman County, Kans.

R.T.D. 3850

Commenced 3/3/55
Completed 3/19/55

| Tops | |
|----------------------|------|
| Kansas City Lime | 3144 |
| Mississippi Chert | 3741 |
| Mississippi Dolomite | 3837 |

Casing Record
8 5/8" Set @ 143' w/120 sx cmt.

----- Figures Indicate Bottom of Formation -----

| | |
|-------------------------|------|
| Surface Soil, Clay | 20' |
| Sand, Clay | 60 |
| Shale & Shells | 143 |
| Shale, Shells & Red Bed | 765 |
| Shale & Shells | 795 |
| Lime & Shale | 1065 |
| Lime, Sandy | 1185 |
| Shale & Lime | 1405 |
| Shale & Lime, Shells | 1530 |
| Lime & Shale | 1750 |
| Shale, Lime, Shells | 1970 |
| Shale & Shells | 2235 |
| Shale & Lime | 3470 |
| Shale & Shells | 2590 |
| Shale & Lime | 3249 |
| Lime | 3482 |
| Lime & Shale | 3699 |
| Lime | 3850 |

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By John R. Fuw...

Subscribed and sworn to before me this 25th day of March, 1955.

Clare L. ...
Notary Public

My Commission Expires 6/17/58

