


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Kingman County, Sec. 2 Twp. 28 Rge. 5 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE
Lease Owner C. V. Phillips
Lease Name Butler Well No. 2
Office Address Hutchinson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-21-61 19____
Plugging completed 6-23-61 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3838 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	144'	None
				5-1/2"	3837'	3249'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3813', sanded to 3795' and dumped 4 sacks of cement @ 3795' with dump bailer. Pulled 5 1/2" casing. Set rock bridge @ 250' and ran 15 sacks of cement @ 250'. Mudded to 140', set 10' rock bridge to 130' and ran 15 sacks of cement @ 130'. Mudded to 30', set 10' rock bridge to 20' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1961

CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss. Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 61

My commission expires May 20, 1964
Milton J. Volin Notary Public.



15-095-01032-0000

Bennett & Roberts Drilling, Inc.
Butler #2

NE SE SE 2-28-5
Kingman County, Kansas

R.T.D. 3838'

Commenced 2/12/55
Completed 2/28/55

Tops	
Cimarron Anhydrite	630
Mississippian Lime	3743
Mississippian Dolomite	3825

Casing Record

8 5/8" Set @ 144' w/115 sx cmt.
5 1/2" Set @ 3837' w/100 sx cmt.

----- Figures indicate bottom of formation -----

Surface Clay	55
Sand & Shells	90
Shale & Shells	144
Red Bed, Shale & Shells	360
Shale & Shells	630
Anhydrite	675
Shells & Shale	710
Shale, Salt & Lime	910
Lime	1000
Lime & Shale	1610
Shale, Lime & Shells	1760
Shale, Lime & Shells	1975
Shale & Lime	3407
Lime	3643
Lime & Shale	3703
Shale	3725
Lime	3834
Chert	3838

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1961

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By [Signature]

Subscribed and sworn to before me this 7th day of March, 1955.

[Signature]
Notary Public

My Commission Expires 6/17/58