


15-095-01467000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec. 2 Twp. 28 Rge. 5W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines NE SW SE  
Lease Owner Bennett & Roberts Oil Operations  
Lease Name Richey Well No. 2  
Office Address Russell, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2/20 19 55  
Application for plugging filed 2/26 verbally 19 55  
Application for plugging approved 2/26 verbally 19 55  
Plugging commenced 2/26 19 55  
Plugging completed 3/1 19 55  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3839 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	131'	None
				5 1/2"	3838'	2998'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock from 3758 to 3735'.  
Dumped 6 sax cement at 3735' with dump bailer, top of cement 3695'. Filled hole with mud to 175', set rock bridge, dumped 25 sax cement, top of cement, 100'. Filled with mud to 20', set rock bridge, dumped 5 sax cement for cap.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 11 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS  
03-11-55

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J & M Casing Pulling Co.  
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst  
Russell, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 55

Clara Hummel  
Notary Public.

My commission expires 6/17/58

PLUGGING  
FILE SEC 2 T 28 R 5W  
BOOK PAGE 101 LINE 40

15-095-0146.7000

Bennett & Roberts Drilling, Inc.  
Richey #2

NE SW SE Sec. 2-28S-5W  
Kingman County, Kansas

R.T.D. 3839'

Casing Record

Comm: 1/26/55  
Comp: 2/11/55

Set 8 5/8" Casing @ 131' with 115 sx. cnt.  
Set 5 1/2" Casing @ 3839' w/ 100 sx. cnt.

Tops:

Cimarron Anhydrite	620'
Mississippian Chert	3744
Mississippian Dolomite	3802

----- Figures Indicate Bottom of Formation -----

Surface Soil, Clay & Sand	80
Red Bed & Shells	131
Shale & Shells	620
Anhydrite	665
Shale & Lime, Shells	790
Lime & Shale	1125
Lime	1245
Lime & Shale	1385
Lime	1480
Lime & Shale	1845
Shale, Lime & Shells	2000
Lime & Shale	2905
Lime	3458
Lime & Shale	3520
Lime	3601
Lime & Shale	3720
Lime	3839

RECORDED & INDEXED  
FEB 15 1955

STATE OF KANSAS )  
RUSSELL COUNTY ) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By John R. Brown

Subscribed and sworn to before me this 15th day of February, 1955.

Clara Hummel  
Notary Public

My Commission Expires 6/17/58

PLUGGING  
WELL SEC 2 1 28 R 5 W  
BOOK PAGE 101 LINE 40