


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec. 4 Twp. 28 Rge. 5 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Trans Era Petroleum, Inc.
Lease Name Ramsdale Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8/29/54 19
Application for plugging filed 8/27/54 19
Application for plugging approved 8/27/54 19
Plugging commenced 8/28/54 19
Plugging completed 8/28/54 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3927 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	164	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 164', set first plug, bridge over with rock, cemented with 15 sacks of cement mixed and run through drill pipe. Filled hole with heavy mud to 25', set second plug at 25', cemented with 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
T. R. Sullivan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.R. Sullivan
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of September, 1954

My commission expires 1-30-57
Margie Cooper Notary Public.

PLUGGING
FILE SEC 4 T 28 R 5W
BOOK PAGE 60 PAGE 9

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1954
CONSERVATION DIVISION
WICHITA, KANSAS

15-095-01472-0000

Trans Era Petroleum, Inc.
Ramsdale #1

SE SW SW 4-28-5
Kingman County, Kansas

Total Depth: 3927'
Comm. 8/13/54
Comp. 8/29/54

Casing

8 5/8" Set @ 164'

Cement

125 sacks of Lehig

FORMATION	DEPTH
Sand-gravel	40
Shale-shells	520
Salt	650
Shale-shells	660
Shale-lime	1050
Shale	1090
Shale-lime	1725
Shale	2080
Shale-lime	2975
Lime	3105
Lime-shale	3150
Lime	3185
Lime-shale	3261
Lime	3377
Lime-shale	3490
Lime	3649
Shale-lime	3770
Lime	3927'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Cora Betz

Subscribed and sworn to before me this 9th day of September, 1954.

Margie Cooper

Notary Public

My commission expires: 1-30-57.

PLUGGING
OCT 4 1954
NOV 9 1954