

STATE OF KANSAS
STATE CORPORATION COMMISSION
205 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-20674 *WOOD*

LEASE NAME Johnson

WELL NUMBER 1

2970 Ft. from S Section Line

3170 Ft. from E Section Line

SEC. 4 TWP. 28 RGE. 5 (E) or (W)

COUNTY Kingman

Date Well Completed 4/8/78

Plugging Commenced 12/12/91

Plugging Completed 12/13/91

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 125 N. Market, #1075 Wichita, KS 67202-1710

PHONE#(316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/9/91 (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Indian Cave Depth to Top 1760 Bottom 1769 T.D. 3797

Show depth and thickness of all water, oil and gas formations.

PBTD 1796

RECEIVED

OIL, GAS OR WATER RECORDS

CASING RECORD KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Indian Cave	Gas	1760	69	8'5/8	215	NONE
				4 1/2	1840	737

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand back 1796 to 1700, spot 4 SX cement 1700-1650. Shot off pipe at 737', spot 35 SX at 700', pull pipe to 300' and circ 100 SX to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 125 N. Market, #1075 Wichita, KS 67202-1710


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gear Petroleum Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, #1075 Wichita, KS 67202-1710



My Commission Expires: 8/1/93

Notary Public

DRILLERS LOG

NOV 26 1991

15-095-20674-0000

No. 1 Johnson "A"

SING RECORD:

COMPANY: Gear Petroleum Company

DESCRIPTION:

5/8" @ 213.51'
175 sx cement

CONTRACTOR: Red Tiger Drilling Company

200' W of SE/4 SE/4 NW/4
Sec. 4-T28S-R5W
Kingman County, Kansas

1/2" @ 1,840
125 sx cement

COMMENCED: March 28, 1978

COMPLETED: April 8, 1978

TOTAL DEPTH: 3,795'

ELEVATION: 1,435' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand & Soil	0	20	
and	20	38	
Hard Sand & Clay	38	58	
Shale	58	132	
Bed	132	215	
Gray Shale	215	685	
Shale	685	924	
Shale w/Lime	924	1189	
Lime	1189	1955	
Lime w/Shale	1955	2111	
Lime	2111	2430	
Lime w/Shale	2430	2630	
Lime	2630	3795	
TD		3795	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 12th day of April, 1978.

Joyce A. Hagermann
Notary Public

