


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Kingman County, Sec. 36 Twp. 28 Rge. 8 (E) 8 (W)
Location as "NE/CNWSWK" or footage from lines SE SW
Lease Owner Whitney Operating Company
Lease Name Bryant Well No. 1
Office Address First National Building - Tulsa, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 25 19 63
Application for plugging filed October 25 19 63
Application for plugging approved October 25 19 63
Plugging commenced October 25 19 63
Plugging completed October 25 19 63
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving - Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4531' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED STATE CORPORATION COMMISSION					
	JUL 29 1964					
	CONSERVATION DIVISION Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 265' with mud, bridged with 1/2 sack hulls and 25 sacks cement. Filled hole to 40' with mud, bridged hole with 1/2 sack hulls and 10 sacks cement. 2 sacks cement in rat hole - 25 sacks cement in mouse hole

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. R. Murfin (Employer or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin
Murfin Drilling Co. - 617 Union Center - Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 19 64

My commission expires _____
ADELA MIZENER, Notary Public
My commission expires November 5, 1966

Adela Mizener
Notary Public.

WELL LOG

15-095-00499-0000

COMPANY Whitney Operating Company

SEC. 36 T. 28S R. 8W

FARM Bryant NO. One

LOG. C/SE SW

RIG. NO. 4

TOTAL DEPTH 4531'


COUNTRY Kingman - Kansas
KANSAS

COMM. 10-8-63 COMP. 10-24-63

SHOT OR TREATED No

CONTRACTOR Murfin Drilling Company

ISSUED



CASING

20 10
15 8 5/8" 272' w/225 sacks
12 6
13 5

ELEVATION 1611 Ground

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

245 Sand & Clay
272 Shale
450 Red Bed
1150 Shale & Shells
1290 Shale with Lime
1375 Shale
1389 Anhydrite
1600 Shale & Shells
1820 Shale & Lime
1950 Lime & Shale
2450 Lime
2615 Lime with Shale
2850 Shale & Lime
2945 Lime
3095 Lime with Shale - Chalky
3200 Lime
3305 Lime & Shale
4130 Lime
4165 Lime & Shale
4215 Cherty Lime
4290 Miss. Chat & Lime
4433 Lime
4482 Lime & Shale - Cherty
4520 Chert
4531 Lime

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1963

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK } ss:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Bryant #1 well.

W. R. Murfin
W. R. Murfin

Subscribed and sworn to before me this 19th day of November 1963

My Commission Expires: ADELA MIZENER, Notary Public
My commission expires November 5, 1966

Adela Mizener
NOTARY PUBLIC