


15-095-00243-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 36 Twp. 28S Rge. 8W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Sierra Petroleum Co., Inc.  
Lease Name Bryant Well No. 1  
Office Address 420 W. Douglas Ave., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 7/8/57 19  
Application for plugging filed 7/7/57 19  
Application for plugging approved 7/7/57 19  
Plugging commenced 7/7/57 19  
Plugging completed 7/7/57 19  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			n	8 5/8	212	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Filled hole from 4580 up to 210' with heavy mud. Set bridge with 1/3 sack hulls, wood plug, 5 gal rock and 20 sacks cement through drill pipe. Filled hole up to 35' with mud. Set bridge with 1/3 sack hulls, wood plug, rock and 10 sacks cement to cellar zero. Job complete 7:30 p.m. 7/7/57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.  
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 10th day of July, 19 57

My commission expires 1-30-61.

Margie Cooper Notary Public.

PLUGGING  
FILE SEC 36 T. 28 R. 8W  
BOOK PAGE 26 LINE 13

RECEIVED  
STATE CORPORATION COMMISSION  
7-11-1957  
JUL 11 1957  
CONSERVATION DIVISION  
Wichita, Kansas

15095-00243-0000

Sierra Petroleum Co., Inc.

BRYANT #1

NE NE NE Sec. 36-28S-8W  
Kingman County, Kansas

Total Depth: 4580'

Elev: 1600 KB

Comm: 6/21/57  
Comp: 7/8/57

Casing:

Cement:

8 5/8" @ 212'

with 150 sacks

FORMATION	DEPTH
Red Bed & shale	500
Shale	1117
Lime & shale	1290
Gyp & shale	1400
Lime & shale	3415
Lime	3488
Lime & shale	3540
Lime	3642
Lime & shale w/chert	3682
Lime w/chert	3722
Lime & shale	4085
Miss	4105
Mississippi Lime	4145
Lime & chert	4263
Shale, lime & chert	4300
Shale	4349
Shale & lime	4433
Lime	4452
Sand, lime & shale	4515
Shale & sand	4548
Arbuckle	4580
Tops:	
Heebner	3084
Douglas	3113
Brown Lime	3297
Kansas City	3310
Mississippi	4068
Kinderhook	4272
Viola	4416
Simpson	4446
Arbuckle	4538

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

C. D. Honaker

Subscribed and sworn to before me this 10th day of July, 1957.

Margie Cooper  
Notary Public

My commission expires: 1-30-61.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 36 T 28 R 8W  
BOOK PAGE 26 LINE 13