


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Kingman County. Sec. 15 Twp. 29S Rge. (E) 5 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE  
Lease Owner PARCO DRILLING, INC. ET AL  
Lease Name GOSCH Well No. I  
Office Address WICHITA KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 7-31-51 19  
Application for plugging filed verbal 7-31-51 19  
Application for plugging approved 7-31-51 19  
Plugging commenced 7-31-51 19  
Plugging completed 7-31-51 19  
Reason for abandonment of well or producing formation D&A  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well RUAL DURKEE  
Producing formation Depth to top Bottom Total Depth of Well 4450 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

SET PLUG NO. 1 A 155' AND CEMENTED W/ 15 SX CEMENT - SET PLUG NO. 2 @ 20' AND CEMENTED W/ 5 SX CEMENT.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to PARCO DRILLING, INC.  
Address 818 CENTRAL BUILDING  
WICHITA KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
D. J. BRIGGS (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) *D. J. Briggs* D. J. Briggs  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of August, 1951.

RECEIVED  
STATE CORPORATION COMMISSION  
*W. M. Gardner*  
Notary Public.

My commission expires March 2, 1953

23-8273-s

4-50-10M AUG 8 X 1951

CONSERVATION DIVISION

PLUGGING  
NE 1/4 SEC 15 T 29 S R 10 W  
BOOK PAGE 109 LINE 10

8-8-1951

**DRILLER LOG**

CONTRACT: Fabco Drilling, Inc et al  
 CONTRACTOR: Fabco Drilling, Inc.

LOCATION: SW SW NE  
 15-29S-3W  
 Kingman, Co.

FARM NAME: Gosh No. 1

COMMENCED: 7-14-51  
 COMPLETED: 7-31-51

6 5/8" CASING USED: 165' 000 w/ 125 ft

Clay & Sand	60
Shale & Shells	105
Shale, Shells, Red Bed	250
Shale & Shells	340
Shale & Lime	1000
Shale, Shells & Lime	1565
Lime & Shale	1745
Lime	2810
Lime & Shale	2905
Sandy Shale	2920
Lime & Shale	3015
Shale & Sand	3117
Shale & Lime	3173
Lime	3310
Shale & Lime	3397
Lime	3470
Lime & Shale	3715
Lime & Chert	4008
Lime	4040
Lime & Shale	4216
Sand	4450
Total Depth	4450

STATE OF KANSAS }  
 SEDGWICK COUNTY } SS:

I, D. J. Briggs, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

FABCO DRILLING, INC.

D. J. Briggs  
 D. J. Briggs, President

Subscribed and sworn to before me this 4th day of August, 1951.

Ruth M. Gardner  
 Notary Public

My commission expires March 2, 1953.

**PLUGGING** Sta. 1  
 SEC 15-29-3W  
 BOOK PAGE 100 LINE 48

AUG 17 1951  
 RECORDS DIVISION  
 Wichita, Kansas