


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Kingman County. Sec. 12 Twp. 28S Rge. 5 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE NW
Lease Owner John C. Graves
Lease Name Jones Well No. 2
Office Address 910 Union Center, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Date Well completed November 17, 1976
Application for plugging filed November 17, 1976
Application for plugging approved November 17, 1976
Plugging commenced November 17, 1976
Plugging completed November 17, 1976
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3825
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 225 feet. Followed by wooden plug and $\frac{1}{2}$ sack hulls. Placed 35 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, $\frac{1}{2}$ sack hulls and 15 sacks cement to base of well cellar. Plugged rat hole with 5 sacks cement.

RECEIVED
NOV 30 1976
11-30-76
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Betty Brandt

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt
910 Union Center, Wichita, Ks. 67202
(Address)

RECORDED AND SWORN TO before me this 29th day of November 1976

My commission expires February 2, 1980

Courtney M. Graves
Courtney M. Graves Notary Public.



15-095-20542-0000

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: 10 Nov. 1976

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: 17 Nov. 1976

CASING RECORD: 5 Jts. 202' of used 8-5/8"
cemented with 175 sacks

LOCATION: Jones No. 2
1/4 SE NW
Section 12-28S-5W
Kingman County, Kansas

0 - 202 Red bed

202 - 1035 Shale & sand

1035 - 1640 Lime & shale

1640 - 2000 Shale & shells

2000 - 2370 Shale

2370 - 2700 Shale & shells

2700 - 2970 Shale

2970 - 3309 Shale & lime

3309 - 3770 Lime & shale

3770 - 3780 Lime

3780 - 3800 Lime & chert

3800 - 3825 Lime

3825 Rotary Total Depth

RECEIVED
NOV 30 1976
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct
to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Courtney M. Graves
Secretary-Treasurer

STATE OF KANSAS)
SEDGWICK COUNTY) - SS:

Subscribed and sworn to before me, a Notary Public, this 29th day of November, 1976

My commission expires: 2 February 1980

Courtney M. Graves Notary Public

