


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-095-30095-0000
Form CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec 12 Twp. 28S Rge. 5W (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Martin & Keller
Lease Name ~~XXXXXXXXXX~~ Jones Well No. 1
Office Address 1035 Kennedy Bldg., Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-18-66 19
Application for plugging filed 10-18-66 19
Application for plugging approved 10-18-66 19
Plugging commenced 10-18-66 19
Plugging completed 10-18-66 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3835 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 214' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 200' - set plug - 1/2 sk. hulls - 25 sks. cement
Mudded to 40' - set plug - 1/4 sk. hulls - 10 sks. cement
2 sks. cem. in rathole

RECEIVED
OCT 24 1966
10-24-66
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1966

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

Ulanda Nichols

DRILLER'S LOG

COMPANY: Martin & Keller
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: JONES #1
 LOCATION: C SW NE SEC. 12-28S-5W
 KINGMAN COUNTY, KANSAS
 COMMENCED: 10-10-66
 COMPLETED: 10-18-66

| | | |
|------|-------------|--------------------------|
| 0 | 50 | Soil & Sand |
| 50 | 214 | Redbed |
| 214 | 550 | Shale & Lime |
| 550 | 1100 | Lime & Shale |
| 1100 | 1325 | Lime |
| 1325 | 1958 | Lime, Shale |
| 1958 | 2330 | Shale, Lime |
| 2330 | 2592 | Lime |
| 2592 | 2877 | Lime & Shale |
| 2877 | 3373 | Lime |
| 3373 | 3475 | Lime & Shale |
| 3475 | 3580 | Shale & Lime |
| 3580 | 3715 | Lime |
| 3715 | 3795 | Shale, Lime |
| 3795 | 3835 | Lime, Chert |
| | <u>3835</u> | <u>RTD - D. & A.</u> |

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 24 1966
 CONSERVATION DIVISION
 Topeka, Kansas

Set 8 5/8" new 20# surface casing @ 214' cemented with 175 sacks
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Jones #1 Well, located
 C SW NE of Section 12, Township 28 South, Range 5 West, Kingman
 County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in
 and for Barton County, Kansas, this 21st day of October, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967