

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
State Required Affidavit
Must be Delivered Report to
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Kingman County, Sec. 1 Twp. 29S Rge. 6 (W)

Location as "NE/CNW/SE/SW" or footage from lines C NE NW
Graves Drilling Co., Inc.

Lease Owner Graves Drilling Co., Inc.

Lease Name Killingsworth Well No. 1

Office Address 910 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 20, 1975

Application for plugging filed June 20, 1975

Application for plugging approved June 20, 1975

Plugging commenced June 20, 1975

Plugging completed June 20, 1975

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	203'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up with heavy mud to 175 feet. Followed by wooden plug and 1/2 sack hulls
Placed 25 sacks cement into hulls. Mudded up with heavy mud to 40 feet followed
by wooden plug, 1/2 sacks hulls and 10 sacks cement to base of well cellar.
Plugged rat hole with 2 sacks cement.

RECEIVED

STATE CORPORATION COMMISSION

JUL 12 1975

6-2-75

DIVISION

Name of Plugging Contractor Graves Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)

Address 910 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss. John C. Graves

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves

910 Union Center, Wichita, Kansas 67202

(Address)

Subscribed and Sworn to before me this 1st day of July, 19 75

My commission expires May 9, 1979

Betty Brandt
Betty Brandt
Notary Public.

Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: June 12, 1975
 910 Union Center
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: June 20, 1975
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 203' of 8-5/8" LOCATION: Killingsworth No. 1
 cemented with 160 sacks C NE NW
 Section 1-29S-6W
 Kingman County, Kansas

0 - 100 Topsoil, river gravel & sans
 100 - 203 Red Bed
 203 - 750 Shale & Shells
 750 - 1205 Shale, shells & lime streaks
 1205 - 1435 Shale
 1435 - 1705 Shale & lime
 1705 - 1934 Lime, shale & sand
 1934 - 2270 Shale
 2270 - 2575 Shale & lime
 2575 - 2790 Shale, lime streaks & some chert
 2790 - 3085 Shale & lime
 3085 - 3629 Lime
 3629 - 3883 Lime shale
 3883 - 3929 Shale
 3929 - 3944 Lime
 3944 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1975

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 1st day of July, 1975

My commission expires: May 9, 1979

Betty Brandt
Betty Brandt Notary Public