

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20,375-0000

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Imperial Oil Co

Complete Address 720 Fourth Financial Center Wichita Kans. 67202

Lease Name Wiltgen Well No. 2-31

Location SW NE NE Sec. 31 Twp. 24 Rge. 17W (East) (West)

County Edwards Total Depth 4530'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated I didn't have an authority to plug this well

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 683

Operation Completed: Hour: 1:00 PM Day: 24 Month: September Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There is 578' of 8 5/8" surface casing cement circulated with 325 dbb of cement. There is 4529' of 4 1/2" production pipe cemented with 195 dbb. Perforations 4457' to 4464'. 1st plug squeezed bottom with 1 shx hulls + 35 dbb cement prepared plug to 4000'. 2nd plug at 600' with 4 shx hulls 10 dbb Jell + 50 shx cement. 3rd plug 7 shx jell released plug to 350' with 35 dbb cement 8 shx Jell. 4th plug 40' to 0' with 15 shx cement. They recovered 2770' of 4 1/2" production pipe. Plugging accomplished by Sun Cementing Great Bend Kansas

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

DATE 10-29-81 SEP 28 1981

CONSERVATION DIVISION  
Wichita, Kansas

Signed: Paul Luther  
Conservation Division Agent