

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM

(File One Copy)

15-155-20,190-0000
H-22/72

API NUMBER _____ (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR EXCALIBUR PRODUCTION CO. INC OPERATOR'S LICENSE NO. 5330 6-92

ADDRESS P.O. Box 278, McPherson KS 67460 PHONE # (316) 241-1265

LEASE (FARM) ENGLAND WELL NO. 1 SW C. SW/4 SE/4
WELL LOCATION 34-23-4W COUNTY Reno

SEC. 34 TWP. 23 RGE. 4W (E) or (W) TOTAL DEPTH 3318 PLUG BACK TD 3318

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 13" SET AT 252 CEMENTED WITH 300 SACKS

CASING SIZE 5 1/2" SET AT 3602' CEMENTED WITH 140 SACKS

PERFORATED AT 3307 ft.

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING plug back with sand to 3300 ft.; 5 sacks cement;

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?
(If not explain.) Drilled prior to 1986

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Pluggger will notify you of date prior to plugging.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 2-12-92

Dennis Gordley PHONE # (316) 463-4833 2 1992

ADDRESS 1108 Glendale, McPherson Kansas 67460

PLUGGING CONTRACTOR KElso Casing Pulling, Inc. LICENSE NO. 6050 6-92

ADDRESS Box 347 Chase, Ks. 67524 PHONE # (316) 938-2943

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Dennis D Gordley
(Operator or Agent)

DATE: 2-10-92

2

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

February 13, 1992

Excalibur Production Co Inc
Box 278
McPherson KS 67460

England 1
API 15-155-20, 190-0060
SW C SW SE
Sec. 34-23-04W
Reno County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #2 202 W First Suite 304
Wichita KS 67202
(316) 263-8809

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

15-155-20196-0000



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

January 25, 1972

COMPANY: EXCALIBUR PRODUCTION COMPANY, INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: ENGLAND #1
 LOCATION: SW C. SW SE, Sec. 34-23E-4W
 Reno County, Kansas
 COMMENCED: January 13, 1972
 COMPLETED: January 22, 1972
 ELEVATION:

0	to	190	Sand
190	to	700	Shale
700	to	845	Shale & Lime
845	to	1230	Lime
1230	to	1855	Shale & Lime
1855	to	2270	Lime & Shale
2270	to	2490	Lime
2490	to	2615	Lime & Shale
2615	to	3145	Lime
3145	to	3255	Shale & Lime
3255	to	3335	Mississippi
3335	to	3455	Lime
3455	to	3515	Lime & Shale
3515	to	3590	Shale
3590	to	3599	Lime
		3599	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 12 1972
 CONSERVATION DIVISION
 WICHITA, KANSAS

Cut 1 1/4 inch hole to 250 ft. and run 252 ft. of 1 1/2 inch surface pipe, cemented with 300 sacks of cement at 250 ft., plug down at 4:00 P. M., January 14, 1972.
 Cut 7 7/8 inch hole to 3599 ft. and run 3602 ft. of 5 1/2 inch pipe, cemented with 140 sacks 2 ft. off bottom at 3597ft. Plug down at 6:00 P. M., January 22, 1972.

TOPS: KANSAS CITY - 2554' MISSISSIPPI - 3255' KINDERHOOK - 3494'
 HUNTON - 3596'

Measurements taken from K. B.


CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. by P. L. Plouffe, do hereby certify that the above and foregoing is a true and correct copy of log on your England #1, located on the SW C. SW SE, Sec. 34-23E-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe, President

by: P. L. Plouffe

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas
 this 25 day of January, 1972.



Johnnie L. Schmidt
 Johnnie L. Schmidt - Notary Public

Commission Expires: June 27, 1973.