

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202  
 STATE CORPORATION COMMISSION

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-155-20,830-0001

LEASE NAME Graber

WELL NUMBER 1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 34 TWP. 23 RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed 10-26-82

Plugging Commenced 11-3-99

Plugging Completed 11-5-99

NOV 16 1999

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

CONSERVATION DIVISION  
 Wichita, Kansas

LEASE OPERATOR Bear Petroleum, Inc.

ADDRESS Box 438, Haysville, KS 67060

PHONE#( 316 ) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well good

(Oil, Gas, D&A, (SWD) Input, Water Supply Well)

The plugging proposal was approved on 10-30-99 (date)

by Doug Lewis (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? no

Producing Formation NA Depth to Top 3440 Bottom 3446 T.D. 3446

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	Surf	233	10 3/4	233	0
	Production Casing	Surf	3699	4 1/2	3699	400

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Dump sand from TD to 3396', pulled stretch on pipe and pipe parted. Pull out 400' casing, perforated from 650-651' 4 shots, ran tubing to 651', spotted 35 sax, pulled tubing to 290', spotted 100 sax, pulled tubing to 250', circulated cement to surface, pulled tubing, and topped well off.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Service, Inc. License No. 3004

Address Box 607, Burrton, KS 67020

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bear Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. A. Schremmer

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) R.A. Schremmer

(Address) Box 438, Haysville, KS 67060

Subscribed AND SWORN TO before me this 15<sup>th</sup> day of November 19 99

R.A. Schremmer  
 Notary Public

My Commission Expires: April 15, 2003





FIELD ORDER No 20003

BOX 438 • HAYSVILLE, KANSAS 67060  
316-524-1225

DATE 11-5 19 99

IS AUTHORIZED BY: BEAR PET (NAME OF CUSTOMER)

Address \_\_\_\_\_ City \_\_\_\_\_ State \_\_\_\_\_

To Treat Well As Follows: Lease GRABER Well No. 1 Customer Order No. \_\_\_\_\_

Sec. Twp. Range SW-SW-NE County RENO State KS

CONDITIONS: As a part of the consideration hereof it is agreed that Copeland Acid Service is to service or treat at owners risk, the hereinbefore mentioned well and is not to be held liable for any damage that may accrue in connection with said service or treatment. Copeland Acid Service has made no representation, expressed or implied, and no representations have been relied on, as to what may be the results or effect of the servicing or treating said well. The consideration of said service or treatment is payable. There will be no discount allowed subsequent to such date. 6% interest will be charged after 60 days. Total charges are subject to correction by our invoicing department in accordance with latest published price schedules.

The undersigned represents himself to be duly authorized to sign this order for well owner or operator.

THIS ORDER MUST BE SIGNED BEFORE WORK IS COMMENCED \_\_\_\_\_ By \_\_\_\_\_  
Well Owner or Operator Agent

CODE	QUANTITY	DESCRIPTION	UNIT COST	AMOUNT
1031	1	<del>dump chgs</del>		400.00
1104	2 SX	<del>cello-flake</del>	10.00	<del>20.00</del>
1030	7	one way mileage		10.50
		* SPOT - 35 SX @ 651' shutdown 1 HR		
		SPOT 100 SX @ 290' shutdown 1/2 HR		
		Cir. cement from 250 - SURFACE		
		RECEIVED STATE COMMISSION NOV 16 1999		
		TK 309/310 400 SX		
		TK 308 115 SX CONSERVATION DIVISION Wichita, Kansas		
3200	515 SX	Bulk Charge 60-40 POZMIX 270 Gal	4.45	2,291.25
3201	14	Bulk Truck Miles 308 /- 309/310		100.00
		Process License Fee on _____ Gallons		
		<b>TOTAL BILLING</b>		

I certify that the above material has been accepted and used; that the above service was performed in a good and workmanlike manner under the direction, supervision and control of the owner, operator or his agent, whose signature appears below.

Copeland Representative \_\_\_\_\_

Station \_\_\_\_\_

Well Owner, Operator or Agent \_\_\_\_\_

Remarks \_\_\_\_\_

KEN'S11999

**NET 30 DAYS**