

#2 API NUMBER 15-155-21091-0000

LEASE NAME Sites

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 34 TWP. 23 RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 7/13/89

Plugging Completed

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Excalibur Production Co., Inc.

ADDRESS P.O. Box 278 McPherson, KS. 67460

PHONE#(316) 463-4833 OPERATORS LICENSE NO. 5330

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3667

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				12 3/4	285	none
				5 1/2	3663	2100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded bottom up to 2840', shot at 2100'. Circulated surface w/ 260 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524 7-25-89

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Excalibur Production Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss STATE CORPORATION COMMISSION

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21 day of July, 19 89

Jane Hoover
 Notary Public

My Commission Expires:





Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

November 20, 1986

15-155-21091-0000

COMPANY:

EXCALIBUR PRODUCTION CO., INC.

CONTRACTOR:

BLACKSTONE DRILLING, INC.

FARM:

SITES #1

LOCATION:

3630' from South Line & 330' from East NE Section 34-23-4W, Reno Co., Kansas

COMMENCED:

November 10, 1986

COMPLETED:

November 19, 1986

ELEVATION:

0	to	140	Sand
140	to	370	Shale
370	to	535	Shale & Lime
535	to	615	Lime
615	to	1260	Lime & Shale
1260	to	1650	Shale
1650	to	2570	Shale & Lime
2570	to	2735	Lime & Shale
2735	to	3470	Lime
3470	to	3582	Lime & Shale
3582	to	3635	Hunton
3635	to	3660	Lime
		3660	T. D.

Cut 17" hole to 283' and run 285' of 12 3/4" casing, cemented with 250 sacks of cement at 283'. Plug down at 8:00 P. M., November 10, 1986. Run 3663' of 5 1/2" casing, cemented with 165 sacks of cement at 3359'. Plug down at 2:45 A. M., November 19, 1986.

TOPS: HUNTON - 3582'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of your log on your Sites #1, located on the NE Section 34-23-4W, Reno County, Kansas.

P. E. Plouffe
P. E. PLOUFFE, PRESIDENT

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 20th day of November 20, 1986.

Johnnie L. Schmidt
JOHNNIE L. SCHMIDT - NOTARY PUBLIC

