

AFFIDAVIT OF COMPLETION FORM

ACO-1

Jan

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Western Drilling & Exploration, Inc. ^{of Arizona} API NO. 15-155-20,831-0000


ADDRESS 439 Wheatland Place COUNTY Reno
Wichita, KS 67235 FIELD Burton

**CONTACT PERSON Donald Bramwell PROD. FORMATION _____
 PHONE 316-722-3174 LEASE Graber

PURCHASER Plugged & abandoned WELL NO. #2
 ADDRESS State Geological Survey WELL LOCATION NE SW NE
WICHITA, BRANCH

DRILLING Aspen Oil, Inc. RECEIVED STATE CORPORATION COMMISSION JUN - 4 1981
 CONTRACTOR _____ 1650 Ft. from E Line and
 ADDRESS 7700 W. Kellogg 1650 Ft. from N Line of
Wichita, KS the 34 SEC. 23S TWP. 4W RGE.

PLUGGING Wayne Webb (Aspen Oil, Inc.) CONSERVATION DIVISION
 CONTRACTOR _____
 ADDRESS 7700 E. 2 Kellogg
Wichita, KS 67207-0412



WELL PLAT
 KCC
 KGS
 MISC _____
 (Office Use)

TOTAL DEPTH 3623 PBTD _____
 SPUD DATE 10/4/81 DATE COMPLETED 10/21/81
 ELEV: GR 1467 DF 1470 KB 1472

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.
 CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	15"	10 3/4"	40 Lbs	199'	Common	200	2% Gel 3% CACL
Production	7 7/8"	8 5/8"	20 lbs	597'	Common	125	2% Gel 3% CACL

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth Interval
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth Interval treated

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____ Gravity _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbis.	bbis.	MCF %	bbis.

Disposition of gas (vented, used on lease or sold) _____ Perforations: _____

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Estimated height of cement behind Surface Pipe Total .

DV USED? None

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Surface Hole	0	144	Indian Cave	1389 + 81
Sand	144	1090	Wabaunsee	1430 + 40
Sand & shale	1090	2079	Stotler	1590 - 120
Shale & lime	2079	2239	Tarkio	1646 - 176
Shale	2239	2539	Elmont	1695 - 215
Lime & shale	2539	3298	Howard	1845 - 375
Shale & chert	3298	3534	Topeka	1965 - 495
Shale	3534	3590	Heebner	2356 - 886
Shale & lime	3590	3623	Br. Lime	2536 -1066
			Lansing	2562 -1092
			K.G. Base	2984 -1512
			Mississippi	3264 -1792
			Kinderhook	3495 -2023
			Hunton	3606 -2134
			RTD	3623 -2151
Plugged & abandoned				
DST #1 3267-3281	15-45-60-45	Weak to fair blow.	Recovered 205' muddy salt water.	
	IFP 68-90 FFP 79-125	ISIP 700 FSIP 620		
DST #2 3611-3623	15-45-60-45	Fair 3" in bucket on both flow periods.	Recovered	
	IFP 55-125 FFP 95-180	ISIP 1212 FSIP 1207		

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS,

Donald G. Bramwell OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (FOR)(OF) Western Drilling & Exploration

OPERATOR OF THE Graber LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 2 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 21 DAY OF October, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Donald G. Bramwell

SUBSCRIBED AND SWORN BEFORE ME THIS 20 DAY OF May 19 82

Patricia A. Brasel
NOTARY PUBLIC

MY COMMISSION EXPIRES:

