

16 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1965
4-14-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Stelbar Oil Corporation Inc.

Complete Address: 310 Petroleum Bldg., Wichita, Kansas

Lease Name Kostner "A" Well No. # 1

Location SE SE NE Sec. 1 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 3999'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 1:30PM Day 13th Month April Year 1965

The Above well was plugged as follows:

261' of 8 5/8" surface pipe, cemented with 200 sacks. 3998' of 5 1/2"
long string, cemented with 100 sacks. Top perferation 3910'. Bottom
of the hole was sanded to 3900', and cemented with 5 sacks. 3350' of
5 1/2" long string was recovered from the hole. Hole was filled with mud
to 260', and 10' of rock bridge, and cemented with 25 sacks. Hole was
filled with mud to 40', and 10' of rock bridge, and cemented with 10
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/14/65
INV. NO. 985-W

Signed: Archie Elving
Well Plugging Supervisor