

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-155-20,847-0000 R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Western Drilling and Exploration

Complete Address 439 Wheatland Pl., Wichita, Kansas

Lease Name Graber Well No. 6

Location 110' E. of NW NE NW Sec. 34 Twp. 23 Rge. 4 (~~East~~)(West)

County Reno Total Depth 592'
New Hole 170'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Lost Hole (Sink Hole)

Plugging Contractor Rosencrantz-Bemis Drilling Co. and United Cementing Co.

Address Box 713, Great Bend, Kansas License No. _____

Operation Completed: Hour: 6:30 PM Day: 21 Month: December Year: 19 81

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows: 8 5/8" - 131' - 100 sacks Common 3% CC.

Hole drilled out to 170'. Communication established with old hole.

Pumped 50 sacks Common cement w/3% c.c. into 8 5/8" casing - no pressure.

Pumped 50 sacks Common cement w/3% cc and 3 sacks hulls into

8 5/8" casing - no pressure. Released 8 5/8" plug. Pumped 50 sacks

Common cement with 3% cc and 1 sack hulls into 8 5/8" casing.

Plug stopped at 143' indicating cement going into old hole

at that point. Pumped 50 sacks common cement into 8 5/8"

Surface casing and closed in at 0" P.S.I. Cement to 12-23-81

10' below ground level. Fill with 2 sacks cement. Total 200 sacks

Cement and 4 sacks hulls.

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 1-21-82

INV. NO. 9104-W