

KANSAS

Form CP-3
Rev. 6-1-66

12

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1976
9-27-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -155 - 20038-0000 (of this well)

Operator's Full Name Woco, Inc.

Complete Address 2225 East 21st Street, Wichita, Kansas 67214

Lease Name Eash-Miller Well No. 2

Location SW NW NW Sec. 34 Twp. 23 Rge. 4 (E) (W) X

County Reno Total Depth 3342'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated (sinking location)

Plugging Contractor Operator and Halliburton Co.

Address License No.

Operation Completed: Hour 3 PM Day 15 Month September Year 1976

The above well was plugged as follows:

Pumped 30 sacks gel w/10 sacks hulls through tubing at 450'. Pumped

35 sacks cement w/1/2 sack calcium chloride through tubing at 450'.

Pumped 50 sacks cement with 1/2 sack calcium chloride through tubing at

450'. Pumped 100 sacks cement w/1 sack flocele through tubing at 450'.

Top of cement at 436' (all of the above was done on 9-14-76)

(9-15-76) Pumped 28 sacks gel w/15 sacks hulls through tubing at 310'.

Pumped 25 sacks cement with 1/2 sack calcium chloride through tubing at

450'--no apparent fill-up. Dumped 8 yards ready mix concrete into 8-5/8"

casing and filled hole to base of celar. Pumped 50 sacks cement into annulu

I hereby certify that the above well was plugged as herein stated.

*450' of 5 1/2" casing removed
by operator before plugging was commenced*

Signed: *Stilwell J. Loren*
Well Plugging Supervisor

INVOICED

DATE 9/29/76

INV. NO. 3884-W