

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-155-02686-0000

FILE NO. 20-22

LOCATION C-SE-SE

SEC. 34 TWP. 23 RGE. 4-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease McPherson

Operator Sohio Petrol. Co Address Box 671 - Russell-Kans

Field _____ County Renno

Total Depth 3379 Feet.

(Describe briefly the manner in which the well was plugged). Cable Tool Hole

Surface Pipe 24"-40ft - 20"-234ft - 15"-237ft. All surface
Pipe left in hole - 8 1/2" casing set at 3020ft - 6" casing set
at 3253ft - 5 3/4" casing set at 3319ft - Plugged back to 3310ft
with cement & Pumped 5 sacks of cement at 3310ft - Shot off &
Pulled the 5 3/4" casing - Shot off & Pulled the 6" casing - Shot
off & started the 8 1/2" casing - Then Kellybenton Pumped in 40 sacks
of heavy mud - Pulled the 8 1/2" casing - Set Back Bridge &
25 sacks of cement at 257ft - Mud to 25ft - Bridge & 10 sacks
of cement at the surface -

Frank Correll Plugging Contractor

PLUGGING
FILE SEC 34 T 23 R 4W
BOOK PAGE 20 LINE 22

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 - 1950 10-9-50

CONSERVATION DIVISION
Wichita, Kansas

District Conservation Agent W. Stough

Date 10-7-50