

KANSAS

V
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

FILED
STATE CORPORATION COMMISSION

AUG 1 1967

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Fred J. Ayosh 15-155-30209.00-01

Complete Address: 438 Wetmore Drive, Wichita, Kansas 67209

Lease Name Mc Elwain Well No. 1

Location NEc SE Sec. 34 Twp. 23 Rge. 4 (E) (W) X

County Reno Total Depth 3593'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:30 PM Day 27 Month July Year 1967

The Above well was plugged as follows:

Hole filled with sand to 3550' and cemented with 5 sacks.

Hole filled with mud to 310'. Rock bridge set from 310' to 300' and hole cemented with 30 sacks. Hole filled with mud to 35'. Rock bridge set from 35' to 25' and hole cemented to base of collar with 15 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. A. L. L. L.
Well Plugging Supervisor

DATE 8/1/67

INV. NO. 6064-W