

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 09 1977
9-9-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-155-20023-0000 (of this well)

Operator's Full Name Midwest Diversified Investment Company

Complete Address 2225 East 21st Street, Suite 205, Wichita, Kansas 67214

Lease Name Miller Well No. 1

Location NW SW NW Sec. 34 Twp. 23 Rge. 4 (E) (W) X

County Reno Total Depth 3340

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 12:30 PM Day 6 Month September Year 1977

The above well was plugged as follows:

4 1/2" liner in hole top at 2520' - Hole in casing just above liner.
Pushed plug to 2520'. Filled hole with sand to 2500' and dumped 6 sacks
cement at 2500'. Casing parted at 677' - pulled 677' of 7" casing.
Dumped 3 1/2 yds ready-mix concrete thru fluid - around top of casing
left in hole. Built rock bridge from 295' to 275' (on fluid) and
filled hole to base of cellar with 5 1/2 yards ready-mix concrete.
Total 9 yards ready mix.
595' of 10 3/4" surface casing cemented with 300 sacks. lost circulation zone 480'

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arthur J. Loman
Well Plugging Supervisor

DATE 9-9-77

INV. NO. 5810-W