

15-095-20072-00-00

Form CP-3
Rev. 6-26-62

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 14, 1968.

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas 67202

Lease Name McKenna "A" Well No. # 1

Location C NE SW Sec. 22 Twp. 28 Rge. 9 (E) (W) W

County Kingman Total Depth 4568'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Kans. License No. _____

Operation Completed: Hour 10:15 AM Day 25th Month February Year 1968

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cement circulated with 160 sacks. Hole was filled with drilling mud to 210', 1st cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 210', and cemented with 24 sacks, with cement from 200' to 125'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30' to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/26/68
INV. NO. 1310-W