

15-095-30088-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1966

CONSERVATION DIVISION
Wichita, Kansas

2-15-1966

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Beat "C" Well No. # 1

Location C NW SE Sec. 36 Twp. 28 Rge. 9 (E) (W) W

County Kingman Total Depth 4541'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Kansas License No.

Operation Completed: Hour 11:15 PM Day 11th Month Feb. Year 1966

The Above well was plugged as follows:

218' of 8 5/8" surface pipe, cement circulated with 145 sacks. Hole
was filled with drilling mud to 200', bridged solid with dry cement
and hulls on fluid at 200', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with dry
cement and hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/15/66

INV. NO. 2725-11