

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20834-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Anador Resources Inc.

Complete Address 5700 S. Quebec, Suite 320, Englewood Colo. 80111

Lease Name Schinstock Well No. 2-16

Location C-NE Sec. 16 Twp. 24 Rge. 20 (East)(West)

County Edwards Total Depth 2625'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was equipped but never produced.

Plugging Contractor Sun Oil Well Cementing Inc

Address Box 169 License No. _____

Operation Completed: Hour: 5:45 PM Day: 31 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They cemented in 2625' of 4 1/2" production pipe cemented within 80' of top. They plugged back to 2622' and perforated pipe from 2591' to 2609'. 1st plug with ~~40~~ 3 sbx. bulbs & 60 sbx of cement. 2nd plug at 1200' with 35 sbx of cement. 3rd plug 40' to 0' with 25 sbx of cement. Then filled hole between surface casing & production pipe to 0' with cement. The plugging was accomplished by Sun Oil Well Cementing.

Amount of Surface Casing: 451' of 7" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

4-6-82

RECEIVED
STATE CORPORATION COMMISSION

INVOICED

Signed: _____
Conservation Division Agent

DATE 4-6-82
INV. NO. 9872-W

APR - 6 1982
CONSERVATION DIVISION
Wichita, Kansas