

JP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John Merritt

Complete Address: P.O. Box 205, Haven, Kansas

Lease Name John Myers Well No. 8

Location C SW NW Sec. 3 Twp. 24 Rge. 4 (E) (W) X

County Reno Total Depth 3398'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 2:30 PM Day 8 Month January Year 1966

The Above well was plugged as follows:

8-5/8" plug pushed to 3310'. Hole filled with sand to 3300' and hole
cemented with 8 sacks. Hole bridged (caved) top 212'. Rock bridge set
from 212' to 200'. Hole bailed to 200' and cemented with 50 sacks.
Hole filled with mud to 35'. Rock bridge set from 35' to 25' and hole
cemented to base of cellar with 25 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: *William J. Loman*
Well Plugging Supervisor

INVOICED

DATE 1/11/66
INV. NO. 2583-U