



15095-20300-000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P.O. Box 17027
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

JUN 4 1973

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Reddick of Gabbert & Jones Inc has this date requested permission to plug the following described well:

Mr. Reddick guarantees payment of the plugging fee.

Operator's full Name: Southern States Petroleum Corp.

Complete Address: 641 Denver Club Bldg 518-17th St. Denver CO

Lease Name: Covington Well No. 1

Location: C NE/SE Sec 31 Twp. 28S Rge. 7 (E)(W) W

County: Kingman Total Depth 4510 Oil well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reddick was instructed to plug the well as follows:
292 ft 8 5/8 surface cemented with 250 sacks. Pump 35 sacks
cement to 260 ft. Mud to 40 ft, plug, 1/2 sack hulls, 15
sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Allied Cementing Co Russell, KS

Very truly yours,

L. Russell Bingham
Conservation Division Agent