

State of Kansas



15-095-01342000 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Feb. 5, 1963

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. C. D. Payne of Kent Well Serviceing Co. has this
date requested permission to plug the following described well:
Inc.

Mr. C. D. Payne guarantees payment of the plugging fee.

Operator's full Name: Sooner Pipe & Supply

Complete Address: Box 574 Tulsa, Oklahoma.

Lease Name: Licklider #1 Well No. #1

Location: 150' E. of C. of SE-NW Sec. 33 Twp. 28 Rge. 7 (E) (W) X

County Kingman County Total Depth 4412' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. C. D. Payne was instructed to plug the well as follows:

4412' of 4 1/2" long string. Bridge plug set at 3905' Top
perforation at 3766'. Hole sanded to 3760' & 3 sacks cement.
257' of 8 5/8" surface pipe circulated with cement. Hole
filled to 200' with mud. 10' rock bridge & 4 yds. Ready-Mix
Cement to base of cellar. 3410' of 4 1/2" pipe recovered.

Very truly yours,

Herman Justus
Conservation Division Agent