

15-095-01341-0000

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: James W. Hershberger

Complete Address: 1039 1st National Bank Bldg., Wichita, Kansas

Lease Name: Robinson Well No. # 1

Location: C N/2 NW SE Sec. 33 Twp. 28 Rge. 7 (E) (W) W

County Kingman Total Depth 4445 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Buffington was instructed to plug the well as follows:

289' of 8 5/8" surface pipe, cemented with 135 sacks.

Fill hole with mud to 280', 1st cementing plug, 1/2 sack hulls,

cement with 20 sacks. Fill hole with mud to 40', 2nd cement-

ing plug, 1/2 sack hulls, cement with 10 sacks to base cellar.

Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent